

PROJECT: GOLD STREET STORM SEWER IMPROVEMENT

General Description:

The Gold Street Storm Sewer Improvement project is located in Alviso along segments of Gold Street, Elizabeth Street, and Moffat Street. The work will include the installation of approximately 340 linear feet of storm drain pipe, manholes, inlets, sidewalk, curb & gutter, and the installation of approximately 173 feet of sanitary sewer pipe.

The existing storm drainage system in this area does not adequately accommodate the volume of local storm water runoff. This results in localized ponding at various locations within the project limits. The implementation of this project will remedy the ponding problem by increasing the size and capacity of the storm drain system.

The project will also extend the existing sanitary sewer line in Gold Street all the way to the storm pump station. This will provide an accessible discharge point adjacent to the pump station in the event that storm waters need to be diverted to the sanitary sewer system due to poor water quality.

Cost: \$440,000 Construction (Estimate)

| | | |
|------------------|----------------|---------------------------------|
| Schedule: | April 2011 | 100% Plans and Specification |
| | May 2011 | Estimated Award of Contract |
| | July 2011 | Estimated Start of Construction |
| | September 2011 | Estimated Beneficial Use |



Project Quick Facts

- Approx. 4,750 sf of sidewalk & driveway
- Approx. 750 lf of curb and gutter
- 2 new ADA compliant curb ramps
- Approx. 340 lf of storm pipe
- Approx. 173 lf of sanitary pipe

Location Map

